


HAZMAT NOTES

1. BUILDING CONTAINS HAZARDOUS MATERIAL (HAZMAT) LOCATIONS. SHOWN ON THIS DRAWING IS A SUMMARY OF ASBESTOS CONTAINING MATERIAL (ACM) LOCATIONS AS CONTAINED IN THE REPORT PREPARED BY RESEARCH MANAGEMENT CONSULTANTS, INC. A SUMMARY OF THIS REPORT IS INCLUDED IN THE SPECIFICATION. THE COMPLETE REPORT IS ON FILE WITH THE FAA.
2. PAINTED AREAS THAT MAY BE DISTURBED BY MODIFICATION ACTIVITIES SUCH AS THE STAIR HANDRAILS ARE ASSUMED TO CONTAIN LEAD-BASED PAINT.
3. REFER TO SPECIFICATION AND APPENDICES FOR STANDARD OPERATING PROCEDURES FOR HANDLING ASBESTOS AND LEAD MATERIALS.
4. INFORMATION PROVIDED IN SPECIFICATION APPENDIX 6 IS FOR OPERATIONS AND MAINTENANCE USE ONLY. ANY BUILDING MATERIAL THAT IS TO BE IMPACTED BY THIS WORK MUST BE SURVEYED FOR ASBESTOS PRIOR TO THE WORK OR ASSUMED TO BE ACM. ASBESTOS SURVEYS SHALL BE PERFORMED IN ACCORDANCE WITH THE FAA SOUTHERN REGION ASBESTOS CONTROL PROGRAM.

SUSPECTED ASBESTOS MATERIAL LOCATION SUMMARY (SEE SPECIFICATIONS FOR ACM REPORT)		
FLOOR LEVEL	ROOM NAME	ASBESTOS MATERIAL (ACM)
FIRST	ENTRANCE STAIR	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC
FIRST	EQUIPMENT	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC; WINDOW CAULK
SECOND	STAIR	WINDOW CAULK
SECOND	TRAFFIC MANAGER	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC; WINDOW CAULK
SECOND	TOILET	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC
THIRD	STAIR	WINDOW CAULK
THIRD	READY ROOM	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC; WINDOW CAULK
FOURTH	STAIR	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC
FOURTH	TOILET	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC; WINDOW CAULK
FOURTH	RUNWAY LIGHT CONTROL	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC; GREY HVAC CAULK
FOURTH	STORAGE	DRYWALL JOINT COMPOUND
FOURTH	CAB STAIR	WHITE/GREY STREAKED FLOOR TILE; TILE MASTIC; CEMENTITIOUS WALL PANEL
CAB	CAB	CEMENTITIOUS WALL PANEL, FOIL BACKING WITH TAR ON TOP OF ROOF HATCH DOOR
CAB	ROOF	ROOF FLASHING; ROOF MASTIC
ALL LEVELS	EXTERIOR	EXTERIOR CAULK; WINDOW PUTTY



HARTRAMPF

7000 CENTRAL PARKWAY, SUITE 1475
ATLANTA, GEORGIA 30328

REV.	LTR.	DATE	DESCRIPTION	CHECKED APPROVED
DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION SOUTHERN REGIONATLANTA, GEORGIA 30320				
AIRPORT TRAFFIC CONTROL TOWER (ATCT) FIRE AND LIFE SAFETY MODIFICATIONS HAZARDOUS MATERIAL (HAZMAT) INFORMATION				
JACKSON		HAWKINS FIELD		MS
REVIEWED BY	SUBMITTED BY	APPROVED BY		
	DESIGNED BY MAS	ISSUED BY ATLANTA NAS IMPLEMENTATION CENTER	DATE - 12-18-2006	REV. LTR.
	DRAWN BY HJM		DRAWING NO. SO-D-103765-H01	
	CHECKED BY RAB			